



RECEIVED

FEB 19 2003

Division of Minerals and Geology

February 17, 2003

Erica Crosby
Colorado Division of Minerals and Geology
Department of Natural Resources
1313 Sherman Street, Room 215
Denver, CO 80203

RE: Permit # M-1977-208
Lyons Quarry
Bonding and Reclamation (Initial submittal) SI-01

Dear Ms. Crosby:

Attached with this letter is the initial bond calculation proposal by Banks and Gesso for the reclamation of the Lyons facility. If the Division agrees with this assessment, CEMEX Inc., Lyons Cement plant will immediately begin the process of obtaining a \$3.9 million bond. To that end, would the Division please supply us with the required Colorado forms so our corporate staff can begin the bonding process.

If there are any questions, please call at 303-823-2113.

Sincerely,

Steve Mossberg
Compliance Manager



Banks and Gesso, LLC

720 Kipling St., Suite 117
Lakewood, Colorado 80215

(303) 274-4277
Fax (303) 274-8329
www.banksandgesso.com

DRAFT

13 February 2003

John Lohr
Plant Manager
Cemex, Lyons Plant
P.O. Box 529
Lyons, CO 80540

RECEIVED

FEB 19 2003

Division of Minerals and Geology

Dear John,

Banks and Gesso, LLC was retained to provide an approximate cost estimate to demolish the Lyons Plant and reclaim the land as discussed in the Reclamation Plan produced by Martin Marietta Cement dated September 1977 (MLRB Permit Number 77-208). The calculation is provided so that a bond amount can be calculated for the reclamation.

Cost Estimate Assumptions

The equipment, steel structures, conveyors, and offices on the site have salvage values greater than the cost of removal. Therefore, the cost of equipment removal or demolition was not included in this calculation under the assumption that it nets to zero dollars.

The calculations for the concrete include all the structures that are above ground surface. Buried foundations, footings, and tunnels were not included in the calculation. However, the building floors and concrete pavement in the plant area were included in the calculation and a uniform thickness of one foot was assumed.

The site was divided into two areas for the estimate; the north part of the site is referred to as the Grinding portion, and the south part is referred to as the Burning portion. This division between the two processes allows a separate bond calculation in the event that the plant is modified so that only the Grinding process occurs in the future. The drawing included with this report depicts the division.

Two cost estimates are presented for razing the plant. Cost Estimate A (Table 1) assumes that all concrete is crushed to various sizes, and that the material is sold as aggregate. For this estimate, the salvage value of the aggregate was conservatively assumed to equal the cost of crushing, thereby saving the disposal cost for this option. Cost Estimate B (Table 2) assumes that the concrete is broken into manageable sizes and is disposed of on the site.

The demolition costs for the buildings on the site were calculated using values based on the volume of the buildings as they stand (Table 3). It was assumed that the interior

floors, columns, foundations, etc., would require additional work, and thus were assigned a separate demolition value based on the volume of concrete.

Quotes for the demolition were collected from Burnett and Sons, Inc. Concrete Crushing and Recycling in Athens, Texas, Porta-Crushers in Littleton, Colorado, and Alpine Demolition in Arvada, Colorado. Also, Means Heavy Construction Cost Data (2001 Edition) was consulted for some of the items.

Grinding Portion

Included in the grinding portion of the plant are the administration building, the mill building, the central control building, raw material silos, and support buildings. The complete lists are included herein on Table 4.

Burning Portion

Included in the burning portion of the plant are the burner building, the coal unloading building and coal silo, the primary and secondary crushers, the bag house, and support buildings. The complete lists are included herein on Table 5

Unit Cost Summary

Estimates for the demolition and disposal are summarized below.

Item Description	Cost
Demolition	
Silo demolition – includes razing silos and transporting material to stockpile	\$70/yd ³
Building demolition - includes razing structures or large foundations and transporting material to stockpile	\$0.30/ft ³ of building volume
Pavement ripping – includes removal of pavement and transporting material to stockpile	\$1.50/ft ²
Aggregate Recycling	
Cost to Crush (per yard)	\$8/yd ³
Salvage Value of aggregate (per yard)	\$8/yd ³
Disposal – includes excavation and placement of material in a pile, and covering with soil	\$10/yd ³
Revegation	\$10,000 per acre of disturbed area

Cost Summary

The total cost of the demolition and reclamation assuming that all material is demolished, stockpiled, and covered and the area is revegetated is approximately \$4.6 million. If all of the aggregate from the concrete can be sold and none of the material is disposed of on the site, the cost is approximately \$3.9 million. No additional scenarios were calculated, such as if only part of the material was sold and some material had to be disposed of on site, or if more marketable grain size aggregate were produced and the aggregate could be sold at a profit rather than a break-even price.

Included with this submittal are the tables that summarize the quantities and the costs used for the work. Included as an Appendix to this report is a set of more detailed calculation sheets that reference the drawings from which the dimensions of structures were taken. A plan view of the site indicating the process area delineation and labels of structures is also attached.

Please contact us with questions regarding this cost estimate or the assumptions that were made. Banks and Gesso, LLC appreciates the opportunity to do this work for the Cemex Lyons Plant.

Regards,
Banks and Gesso, LLC



M. Danelle Volpe, PE

enc: Tables 1,2,3,4 & 5
Drawing
Appendix of calculations

Table 1
Demolition and Reclamation Cost
Estimate A

Structure	Quantity	Grinding Process		Total Cost
		Units	Cost	
Pavement demolition	600,000	s.f.	\$1.50	\$900,000
Pavement disposal	22,222	c.y.	\$0	\$0
Large foundations demolition	2,698	c.y.	\$30	\$80,940
Large foundations disposal	2,698	c.y.	\$0	\$0
Buildings demolition	1,712,001	c.f.	\$0.25	\$428,000
Buildings disposal	5,667	c.y.	\$0	\$0
Silos demolition	8,463	c.y.	\$70	\$592,410
Silos disposal	8,463	c.y.	\$0	\$0
Revegetation of disturbed areas	15	acres	\$10,000	\$150,000
<u>Total Cost Burning Process</u>				<u>\$2,151,350</u>

Structure	Quantity	Burning Process		Total Cost
		Units	Cost	
Pavement demolition	600,000	s.f.	\$1.50	\$900,000
Pavement disposal	22,222	c.y.	\$0	\$0
Large foundations demolition	3,768	c.y.	\$30	\$113,040
Large foundations disposal	3,768	c.y.	\$0	\$0
Buildings demolition	1,185,760	c.f.	\$0.25	\$296,440
Buildings disposal	2,230	c.y.	\$0	\$0
Silos demolition	4,070	c.y.	\$70	\$284,900
Silos disposal	4,070	c.y.	\$0	\$0
Revegetation of disturbed areas	15	acres	\$10,000	\$150,000
<u>Total Cost Grinding Process</u>				<u>\$1,744,380</u>

DRAFT

Table 2
Demolition and Reclamation Cost
Estimate B

Structure	Quantity	Grinding Process		Total Cost
		Units	Cost	
Pavement demolition	600,000	s.f.	\$1.50	\$900,000
Pavement disposal	22,222	c.y.	\$10	\$222,222
Large foundations demolition	2,698	c.y.	\$30	\$80,940
Large foundations disposal	2,698	c.y.	\$10	\$26,980
Buildings demolition	1,712,001	c.f.	\$0.25	\$428,000
Buildings disposal	5,667	c.y.	\$10	\$56,670
Silos demolition	8,463	c.y.	\$70	\$592,410
Silos disposal	8,463	c.y.	\$10	\$84,630
Revegetation of disturbed areas	15	acres	\$10,000	\$150,000
<u>Total Cost Burning Process</u>				<u>\$2,541,852</u>

Structure	Quantity	Burning Process		Total Cost
		Units	Cost	
Pavement demolition	600,000	s.f.	\$1.50	\$900,000
Pavement disposal	22,222	c.y.	\$10	\$222,222
Large foundations demolition	3,768	c.y.	\$30	\$113,040
Large foundations disposal	3,768	c.y.	\$10	\$37,680
Buildings demolition	1,185,760	c.f.	\$0.25	\$296,440
Buildings disposal	2,230	c.y.	\$10	\$22,300
Silos demolition	4,070	c.y.	\$70	\$284,900
Silos disposal	4,070	c.y.	\$10	\$40,700
Revegetation of disturbed areas	15	acres	\$10,000	\$150,000
<u>Total Cost Grinding Process</u>				<u>\$2,067,282</u>

DRAFT

Table 3
Airspace of Buildings

Building	length	width	height	volume of building (ft^3)		Burning Demolition	Grinding Demolition
✓ Bag house	130	60	45	351,000	burning	351,000	
✓ Pack house	150	72	25	270,000	grinding		270,000
Pack house	45	41	36	66,420	grinding		66,420
Crusher control building	10	10	10	1,000	burning	1,000	
✓ Administration building	120	65	24	187,200	grinding		187,200
Administration building	105	46	14	67,620	grinding		67,620
✓ Mill Building	168	97	53	863,688	grinding		863,688
✓ Burner Building	120	91	53	578,760	burning	578,760	
Burner Building	48	91	25	109,200	burning	109,200	
✓ Control Center	88	37	38	123,728	grinding		123,728
Control Center	37	34	20	25,160	grinding		25,160
✓ Pump house	25	25	15	9,375	grinding		9,375
✓ Wash house	10	10	8	800	grinding		800
✓ Coal Unloading Building	71	36	30	76,680	burning	76,680	
✓ Labor shed	96	40	18	69,120	burning	69,120	
✓ Electrical Room	26	15	15	5,850	grinding		5,850
✓ Miobil Equipment Shed	96	32	30	92,160	grinding		92,160
Total						1,185,760	1,712,001

Table 4
Volumes of Concrete in Grinding Area

Grinding Area Structures		Concrete In-Place (yd³)	Silos (yd³)	Buildings (yd³)	Foundations (yd³)
Administration Building	Exterior walls	236		236	
	Interior Walls	256		256	
	Additional Floors	7			7
	Roof	233		233	
Mill Building	Exterior walls	733		733	
	Interior Walls	31		31	
	Additional Floors	114			114
	Roof	416		416	
	Beams	189			189
	Columns	320			320
	Mill Foundations	1,217			1,217
	Additional Foundations	13			13
Control Center	Exterior walls				
	Interior Walls				
	Additional Floors	160			160
	Roof	103		103	
Raw Material Silos		1,134	1,134		
Clinker Storage Building	Walls/Roof	2,629		2,629	
	Additional foundations	80			80
	Outside Clinker Pit	101			101
	Marginal Clinker	33			33
Pack House	Exterior walls	446		446	
	Additional Floors	442			442
	Roof	311		311	
	Columns	22			22
Finished Cement Silos		7329	7,329		
Mobil Equipment Shed		190		190	
Electrical Room		38		38	
Wash House		8		8	
Pump House		37		37	
Total		16,828	8,463	5,667	2,698

Table 5
Volumes of Concrete in Burning Area

Burning Area Structures		Concrete In- Place (yd³)	Silos (yd³)	Buildings (yd³)	Foundations (yd³)
Burner Building	Exterior walls	509		509	
	Additional floors	199		199	
	Roof	223		223	
	Piers	3,083			3083
	columns	8			8
	Additional Foundations	35			35
Primary Crusher	Exterior walls	265		265	
	Divider wall	24			24
	Control bldg walls	7		7	
	Roof	416		416	
Secondary Crusher	Silos	342	342		
	Additional floors	60			60
Homogenizing Silos		1,637	1637		
Coal	Coal Silo	1,115	1115		
	Coal Unloading Building	159		159	
	Additional Foundations	19			19
	Cyclone Foundation	32			32
Stack		976	976		
Bag House	Columns	276			276
	Walls	422		422	
Raw Material Dryer	Dryer Bldg Walls	30		30	
	Foundations	155			155
Additional Foundations		76			76
Total		10068	4,070	2230	3768

Appendix Calculations

ADMIN BLDG

WALLS - PRESTRESSED CONCRETE PANELS ^{OR} CONCRETE BLOCK

PERIMETER WALLS

BLOCK WALL 262 LF X 8" X 14' HIGH
COLUMNS 22 - 8" X 1.5 FT X 14' HIGH
251 LF X 4" X 24' HIGH
T'S 63 - 8" X 1.6' X 24' HIGH

91 yd³
11 yd³
74 yd³
60 yd³ } 236 yd³

INTERIOR

742 LF X 8" X 14' HIGH
=

REFERENCE

DWG

41-1-A

41-4-A

256 yd³

ADD'L FLOOR

33' X 12' X 6" = 7.3

ROOF - 120' X 65' X 6" = 144
46' X 105' X 6" 89

241 yd³

MILL BUILDING

EXTERIOR WALLS - PRESTRESSED CONCRETE

2 - 120' X 53' X 4" =
91' X 53' X 4" =
60 - 1.6 X 53' X 8" =
30 - 1.6 X 53' X 8" =

LOW ROOF

(T'S)

(T'S)

157 yd³
60 yd³
126 yd³
63 yd³

405 yd³

REFERENCE
DRAWINGS

2 - 48' X 91' X 4"
25' X 91' X 4"
78' X 91' X 4"
24 - 1.6 X 53' X 8"
6 - 1.6 X 53' X 8"
20 - 1.6 X 53' X 8"

HIGH ROOF

(T'S)

(T'S)

(T'S)

108 yd³
28 yd³
88 yd³
50 yd³
13 yd³
42 yd³

03-01-CC

03-05-CC

03-04-CC

328 yd³

INTERIOR WALLS

1.5' X 31 LF X 18 FT HIGH 31 yd³

REFERENCE DWG
03-01-CC

INTERIOR FLOOR - MOTOR ROOM

35' X 35' X 6" 03-5-CC 23 yd³

03-1-CC

152 yd³

MILL BLDG. CONTINUEDPREFCAST BEAMS

1.3' x 2.3' x 93 B-3, B-4
 1 x 2.2 x 93 B-5, B-6, B7
 1 x 1.8 x 66 B-1, B2

REF. DWG

03-2-CC

10 yd³
 8 yd³
 4 yd³ } 22 yd³

COLUMNS

14 - 2'8" x 2'8" x 80' HIGH
 14 - 1' x 1' x 50' HIGH

REF. DWG.

03-1-CC

295 yd³
 26 yd³ } 320 yd³

RAW MILL FOUNDATION

46' x 4' x 20' BOTTOM SLAB 13 yd³
 18' x 14' x 26' SYMETRIC DRIVE 243 yd³
 9' x 9' x 26' 78 yd³
 18' x 5' x 16' STATIONARY DRIVE 53 yd³
 16' x 5' x 16' MOVEABLE BEARING 47 yd³

REF. DWGS.

03-8-CC

03-10-CC

557 yd³FINISH MILL FOUNDATION

88' x 4' x 28' BOTTOM SLAB 365 yd³
 20' x 13' x 28' SYMETRIC DRIVE 270 yd³
 5' x 9' x 28' 47 yd³
 16' x 5' x 17' STATIONARY BEARING 50 yd³
 16' x 5' x 10' MOVEABLE BEARING 30 yd³

REF. DWGS.

03-8-CC

03-9-CC

726 yd³MILL BLDG ROOF

97' x 168' x 6"
 24 - 2' x 8" x 97' (T's) 301 yd³
 115 yd³

03-1-CC

416 yd³ADDITIONAL FOUNDATIONS

3 - 10' x 3' x 4' - No dwg 13 yd³

13 yd³BEAMS SUPPORTING SEPARATOR FLOOR

2 - 5' x 3' x 86' 96 yd³
 5 - 3' x 3' x 43' 72 yd³

03-3-CC

167 yd³SLAB AROUND SEPARATOR

1' x 75' x 48 - (3 * 9²π + 7.5²π + 20' x 10')

03-3-CC 91 yd³= 2229 yd³

CONTROL CENTERWALLS - CONCRETE BLOCK

- 2 - 37' x 38' ^{HIGH} x 8"
2 - 88' - 38' ^{HIGH} x 8"
2 - 34' x 20' ^{high} x 8" Penthouse
2 - 37' x 20' ^{high} x 8" "

REF DWG
47-1-CC

69 yd³
165 yd³
34 yd³ 305 yd³
37 yd³

ADD'L FLOORS

- 2 - 88' x 37' x 4"
44 - 8" x 2' x 37' (T's)

80 yd³ 160 yd³
80 yd³

ROOF

- 88' x 37' x 4" (also 3'd floor below penthouse)
22 - 8" x 2' x 37' T's
25' x 37' x 4" penthouse
6 - 8" x 2' x 37' T's

40 yd³
40 yd³ 103 yd³
11
11 yd³

568 yd³

BURNER BUILDINGPIERS

#1	10' x 29' x 22'
#2	13' x 23' x 29'
#3	40' x 25' x 29'
	19' x 25' x 35'
#4	13' x 23' x 35'
#5	13' x 24.5' x 38'

- Added later

236 yd³
321
1074
616
388
448

REF. DWG.

OS-1-CC
OS-3-CC3083 yd³COLUMNS

11 - 2' x 2' x 53'

REF DWG.

OS-1-M

8 yd³ADD'L ENDS

4 - 3' x 4' x 12'
3 - 2' x 10' x 3'
6 x 10 x 3

21 yd³
7
7

No drawing

35 yd³ROOF

69' x 4" x 128'
18 - 8" x 2' x 128'

T's

109 yd³
114 yd³

OS-12-CC

223 yd³WALLS

2 - 128 x 4" x 53'
2 - 69' x 4" x 53'
64 - 8" x 2' x 53'
32 - 8" x 2' x 53'

T's
T's

168 yd³
90 yd³
168 yd³
84 yd³

REF DWG

OS-12-CC

509 yd³INTERIOR FLOOR

1' x 47' x 114

OS-12-CC 199 yd³4056 yd³

PRIMARY CRUSHER

WALLS

WALLS - 2 - 43' x 2' x 30' high
 REAR 20' x 2' x 30' high
 PIERS 6 - 1.1' x 0.9' x 6' high
 5' x 1.0' x 18' high
 WINGS 2 - $\frac{1}{2}$ (18x29) x 1.3'

ROOF - CRUSHER

32' x 22' x 4" 9 yd³
 8 - 8" x 2' x 22' T's 9

CONTROL BLDG

3 - 10' x 10' x 8" WALLS

DIVIDER WALL

23' x 2' x 14'

REF DWGS 191 yd³
 02-2-CC 44
 02-1-CC 1
 02-3-CC 3

25
 265 yd³

18 yd³

200 yd³

24 yd³

507 yd³

FLOORS/LOTS - ASSUME ALL AREA IS PAVED 1 FT THICK

SECONDARY CRUSHER

SEE "SILOS" FOR EXTERIOR CALC'S

ADD'L FLOORS

2 - $\left(\frac{32}{2}\right)^2 \pi \times 1' - \text{CRUSHER SILO}$

REFERENCE DWG
02-6-M

60yd³

RAW MATERIAL DRYER

DRYER BLDG

2 - 21' x 16' ^{high} x 8"
2 - 16' x 16' x 8"

17yd³
13

02-9-CC
02-10-1C

30yd³

DRYER FOUNDATION

5' x 15.5' x 13' 37
16.5' x 9' x 13' 72
7' x 9' x 2.5' 6
15.5' x 5' x 14' COLUMN 40



155yd³

244yd³

SILOS

NAME	DIAM	WALL THK	HEIGHT	VOLUME
RAW MAT'L 1	27'	7"	73'	130 yd ³
2	↓	↓	↓	↓
3	↓	↓	↓	↓
4	↓	↓	↓	↓
5	↓	↓	↓	↓
6	↓	↓	↓	↓
CLINKER 1	27'	7"	73'	130 yd ³
2	↓	↓	↓	↓
3	↓	↓	↓	↓
STACK (NO DWG)	44' OCTAGON	12"	195'	976
HOMOGEN. SILOS - HOMOGEN.	40'	1.5'	142'	954
REF 04-1,2,3,4-CL	31'	1.33'	142'	614
KILN DUST	20'	7"	52'	69
COAL SILO	50'	0.9'	135'	707

ADD'L CONCRETE:

PLAN



$$\text{Volume of cylinder} = \pi r^2 h = \pi (25)^2 (23) = 45,160$$

$$\text{Vol. of cone} = \frac{1}{3} \pi r^2 h = \frac{1}{3} \pi (25)^2 (23) = 15,053$$

$$\text{Vol cylinder} - \text{volume of cone} = 1115 \text{ yd}^3$$

NAME	DIAM	WALL THICK	HEIGHT	VOL
FINISHED CEMENT A1	20' OD	1.0'	150'	332
A2	↓	↓	↓	↓
A4	↓	↓	↓	↓
REF DWGS A5	↓	↓	↓	↓
08-6-CC/ A7	40'	1.67'	↓	1115
08-5-CC/ A9	20'	1.0'	↓	332
08-4-CC A10	↓	↓	↓	↓
A12	↓	↓	↓	↓
A13	↓	↓	↓	↓
B1	40'	1.67'	↓	1115
B2	20'	1.0	↓	332
B3	↓	↓	↓	↓
B5	↓	↓	↓	↓
B6	↓	↓	↓	↓
B7	40'	1.67	↓	1115
SECONDARY CRUSHER DUST	26' (ID)	7"	85	750
02-5-M CRUSHER	32	8"	55	1134
02-8-CC SURGE	20	7"	44	58
				12,125 yd ³

BAGHOUSECOLUMNS-

30-1.75' x 1.75' x 21'
40-1.75' x 1.75' x 45'

72 yd³
204 yd³

05-17-CC

276 yd³WALLS

2- 60' x 8" x 45'
2- 130' x 8" x 45'

133 yd³
289

422 yd³PACKHOUSEWALLS

2- 150' x 4" x 25'
75- 8" x 2' x 25'
2- 72' x 4" x 25'
36- 8" x 2' x 25'
2- 41' x 4" x 45'
20- 8" x 2' x 45'
2- 36' x 4" x 45'
9- 8" x 2' x 45'

7's 93 yd³
93 yd³
44 yd³
44 yd³
46 yd³
46 yd³
40 yd³
40 yd³

REF DWGS

09-1-CC

09-3-CC

446 yd³INTERIOR FLOORS

3- 41' x 36' x 1'
1- 100' x 75' x 1'

164 yd³
278 yd³

442 yd³ROOF

150' x 84' x 4"
21- 8" x 2' x 150'

156 yd³
156 yd³


311 yd³COLUMNS

2- 2' x 1' x 25'
2- 2' x 1.5' x 70'
1- 1' x 1' x 70'

4
16
3

22 yd³1919 yd³

CLINKER STORAGE BLDG



L = 388'

$\frac{1}{2}(2) 100 (79.2) \times 4"$	- CLOSED END	98 yd ³
25 - 8" x 2' x 79'	7's	98 yd ³
2 - 127 x 388 x 4"	ROOFS	1217 yd ³
194 - 8" x 2' x 127	T's	1217 yd ³
		<u>2429 yd³</u>

CONVEYOR - ABOVE GROUND

50 yd ³	- TUNNEL		80 yd ³
30 yd ³	HOPPER	NO DWG	

COAL UNLOADING BLDG

2 - 71' x 30' x 4"		53 yd ³	
36 - 2' x 8" x 30'	7's	53 yd ³	159 yd ³
2 - 36' x 30' x 4"		27 yd ³	
9 - 2' x 8" x 30'	7's	27 yd ³	

LABOR SHED

2 - 96' x 18' x 4"		43 yd ³	
48 - 2' x 8" x 18'		43 yd ³	122 yd ³
2 - 40' x 18' x 4"		18 yd ³	
20 - 2' x 8" x 18'		18 yd ³	

MOBILE EQUIPMENT SHED

2 - 32' x 30' x 4"		24 yd ³	
16 - 8' x 2' x 30'		24 yd ³	
2 - 96' x 30' x 4"		71 yd ³	
48 - 2' x 8" x 30'		71 yd ³	190 yd ³

ELECTRICAL ROOM

2 - 22' x 15' x 4"		9 yd ³	
12 - 8' x 2' x 15'		9 yd ³	
2 - 26' x 15' x 4"		10 yd ³	38 yd ³
14 - 8' x 2' x 15'		10 yd ³	

3217 yd³

PUMP HOUSE

4 - 25 x 15 x 3"

NO DWGS

37 yd³

ADDL FNDNS

COAL CYCLONE

18' x 24' x 2'

32 yd³

DRYER FOUNDATION

3.5 x 9' x 16'

19 yd³

PIERS

6 - 2' x 1.5' x 7'
4' x 10' x 10'
4 - 5' x 2.5' x 2.5'
2 - 3' x 2.5' x 2.5'
13 - 2.5 x 2.5 x 12'
10' x 5' x 4'
2 - 2.5 x 10' x 4'

DUST COLLECTOR
FOUNDATIONS
ALONG EAST SIDE

FAN

5 yd³
15 yd³
5 yd³
1 yd³
36 yd³
7 yd³
7 yd³

76 yd³

OUTSIDE CLINKER PT

2 - 21' x 15' x 15'
27' x 15' x 15'
27' x 15' x 15' - (25 x 14 x 14)

35 yd³
22 yd³
44 yd³

101 yd³

MARGINAL CLINKER

3 - 20' x 15' x 1

33 yd³

COAL SILO

10' x 10' x 5'

19 yd³

WASH HOUSE

4 - 10' x 8' x 8"

8 yd³

325 yd³