

STATE OF COLORADO

DIVISION OF MINERALS AND GEOLOGY
Department of Natural Resources

1313 Sherman St., Room 215
Denver, Colorado 80203
Phone: (303) 866-3567
FAX: (303) 832-8106



Bill Owens
Governor

Greg E. Walcher
Executive Director

Ronald W. Cattany
Division Director

FAX COVER SHEET (Fax # 303-832-8106)

TO: Danella Volpe

CO./AGENCY: Banks & Gesso

No. of Pages Sent: 3

FROM: Erica Crosby

FAX NO.: (303) 274-8329

MESSAGE TO RECIPIENT:

Danella,

Attached is the info. you requested for demo. costs associated w/ the CEMEX reclamation cost estimate (conveyor demo. & bentomat/geosynthetic clay liner). Also, a letter sent to CEMEX regarding on-site disposal of demo. debris.

Please call if you have any questions.

Erica

DATE: 4-2-03

PROGRAM: MINS. ☒ COAL ☐ AML ☐ M. SAFETY ☐

TIME TO BE SENT: ASAP ☒ or NIGHT RATE ☐

DEMOLITION MENU - CONVEYORS, POWERLINES, FENCES, RAILINGS and RR TRACKS**INSTRUCTIONS:**

Using the keyboard arrow keys, position the cellpointer over the desired item description (items in bold red text).
Press the ENTER key to record your selection.

DATA SOURCES: MEANS Site Work & Landscape Cost Data, Ed. 2003, Sec. 02220.

Conveyor & powerline removal costs from DMG constr. contract data (cost indexed to current yr. per MEANS Historic Cost Index).

NOTE: Costs shown do NOT include demolished material disposal costs or dump fees.

CONVEYORS - Dimensions shown are outside housing, NOT belt width. Conveyor support removal included (foundation removal not incl.).

No. CY Rubble per conveyor LF est. at 50% of housing vol., e.g. 5' x 6' = 30 CF per LF / 27 = 1.11 CY / LF x .50 = .5556 CY rubble/LF.

NOTE: Use the KEYBOARD, not the MOUSE, to make a selection.

...table continues beyond bottom of screen

ITEM DESCRIPTION	UNIT OF MEASURE	CY Rubble PER UNIT	UNIT COST
HELP			
BACK			
Conveyor, elevated, including supports - 5 ft. W x 6 ft. H housing	LF	0.55556	\$31.85
Conveyor, elevated, including supports - 8 ft. W x 10 ft. H housing	LF	1.48148	\$38.22
Conveyor, overland, including supports - 5 ft. W x 6 ft. H housing	LF	0.55556	\$12.75
Conveyor, overland, including supports - 8 ft. W x 10 ft. H housing	LF	1.48148	\$19.12
Powerline or telephone line, overhead, wood - Single pole	LF	NA	\$2.14
Powerline or utility line, overhead, wood - Double or "H" pole	LF	NA	\$4.30
Powerline or utility line, overhead - Structural steel box type frame	LF	NA	\$26.82
Fencing, barbed wire, - 3 strand	LF	NA	\$0.92
Fencing, barbed wire, - 5 strand	LF	NA	\$1.41
Fencing, chain link, including posts and fabric - 8 ft. to 10 ft. high	LF	NA	\$1.94
Fencing, chain link, including posts and fabric - to 6 ft. high	LF	NA	\$1.66
Fencing, wood, all types - 4 ft. to 6 ft. high	LF	NA	\$0.91
Fence post, wood, 4 in. x 4 in. - 6 ft. to 8 ft. high	EA	NA	\$4.11
Fence rail, wood, 2 in. x 4 in. - 8 ft. long	LF	NA	\$0.05
Railing, roadside guiderail only - Corrugated steel	LF	NA	\$7.28
Railing, roadside guiderail posts only	EA	NA	\$8.70
Railing, roadside guiderail and posts (posts on 20 ft. centers)	LF	NA	\$7.72
Railroad track - Ties and track	LF	NA	\$6.52
Railroad track - Ballast	CY	1.00000	\$2.94

Cost for bentomat or geosynthetic clay liner \$3.60/sy