



999

Is your RETURN ADDRESS completed on the reverse side?

SENDER:

- Complete items 1 and/or 2 for additional services.
- Complete items 3, 4a, and 4b.
- Print your name and address on the reverse of this form so that we can return this card to you.
- Attach this form to the front of the mailpiece, or on the back if space does not permit.
- Write "Return Receipt Requested" on the mailpiece below the article number.
- The Return Receipt will show to whom the article was delivered and the date delivered.

I also wish to receive the following services (for an extra fee):

1. ☐ Addressee's Address
2. ☐ Restricted Delivery

Consult postmaster for fee.

3. Article Addressed to:

Mr John Lohe
Southdown Inc
P.O. Box 529
Lyons Co 80504

4a. Article Number

P 213 351 865

4b. Service Type

- ☐ Registered ☒ Certified
☐ Express Mail ☐ Insured
☐ Return Receipt for Merchandise ☐ COD

7. Date of Delivery

7-16-97

5. Received By: (Print Name)

M Demay

6. Signature: (Addressee or Agent)

X M Demay

8. Addressee's Address (Only if requested and fee is paid)

PS Form 3811, December 1994

Domestic Return Receipt

Thank you for using Return Receipt Service.

Spec. CLIP 213 351 865
File 1-77-341
US Postal Service
Receipt for Certified Mail
No Insurance Coverage Provided.
Do not use for International Mail (See reverse)

Sent to
Mr John LoheStreet & Number
PO Box 529Post Office, State & ZIP Code
Lyons Co 80504

Postage \$

Certified Fee

Special Delivery Fee

Restricted Delivery Fee

Return Receipt Showing to Whom & Date Delivered

Return Receipt Showing to Whom, Date, & Addressee's Address

TOTAL Postage & Fees \$

Postmark or Date

PS Form 3800, April 1995

DMG-1212 Sherman, Bm. 215 Denver CO 80203

PERMIT NUMBER : M-77-341 PREP. BY: CLK FILENAME: M341-0

DATE : 07-May-97 OPERATION: Larimer County Quarry

PERMIT ACTION : Succession of Operations

GRAND TOTAL BOND AMOUNT : \$26,725

I. DIRECT COSTS

A. EARTHWORK - BACKFILLING & ROUGH GRADING

[illegible]

Subtotal (A) :

B. EARTHWORK - HIGHWALL REDUCTION

[illegible]

Subtotal (8) :

C. EARTHWORK - WASTE PILE COVER PLACEMENT

Task No.	Task Description	Cost (\$)

Subtotal (C) :

[illegible]

=====

[illegible]

=====

[illegible]

=====

[illegible]

● 2010年10月10日

[illegible]

[illegible][illegible][illegible]

=====

K. PORTAL/SHAFT SEALING

Task No.	Task Description	Cost (\$)

Subtotal (K):

=====

L. DRILL HOLE/MONITORING WELL SEALING

Task No.	Task Description	Cost (\$)

Subtotal (L):

=====

M. MISCELLANEOUS RECLAMATION TASKS

Task No.	Task Description	Cost (\$)
	Demolition	
3	Seeding	\$22,142
	Fencing	
4	Mob/Demob	\$477

Subtotal (M): \$22,619

=====

TOTAL DIRECT RECLAMATION COSTS (subtotals A through M): \$22,619

=====

II. INDIRECT COSTS

=====

A. CONTRACTOR'S OVERHEAD & PROFIT

Item No.	Item Description	Cost (\$)
1.	Public Liability Insurance.... 1.550% of dir.	\$351
2.	Contractor's Performance Bond 0.975% of dir.	\$221
3.	Contractor's Profit..... 10.00% of dir.	\$2,262
4.	Job Superintendent .	

Subtotal (A): \$2,833

=====

TOTAL CONSTRUCTION CONTRACT AMOUNT (direct plus O & P): \$25,452

=====

B. DMG PROJECT ADMINISTRATION EXPENSES

Item No.	Item Description	Cost (\$)
1.	Minerals Program Adm 5.00% of cntr.	\$1,273

NET INDIRECT COST PERCENTAGE: 18.15% Subtotal (B): \$1,273

=====

TOTAL INDIRECT RECLAMATION COSTS (subtotals A through B): \$4,106

=====

TOTAL PERFORMANCE BOND AMOUNT (direct plus indirect costs): \$26,725

=====

ESTIMATING FORM - REVEGETATION WORK

Task Number : 3

Prepared By : CLK

Filename : M341-3

Date : 07-May-97

Permit Number : M-77-341

Operation : Larimer County Quarry

Permit Action : Succession of Operations

Task Description : Seed 40 acres

A. SEED MIX

SPECIES NAME - COMMERCIAL VARIETY	SCIENTIFIC NAME	RATE-PLS LBS/ACRE	NATIVE/ INTRODUCED	W/C SEASON	SEEDS/ SQ.FT.	COST PLS/ACRE
GRASSES:						
Perennial ryegrass - All Star	Lolium perenne	19.50	Introduced	Cool	110.6	\$25.28
Smooth brome - Achenbach	Bromus inermis	4.50	Introduced	Cool	15.0	\$6.94
Intermediate wheatgrass - Amur	Agropyron intermedium	4.00	Introduced	Cool	8.5	\$4.32
Russian wildrye - Bozolsky	Elymus junceus	3.00	Introduced	Cool	12.1	\$12.04
Crested wheatgrass - Nordan	Agropyron desertorum	4.00	Introduced	Cool	16.1	\$3.40
Tall wheatgrass - Jose	Agropyron elongatum	5.00	Introduced	Cool	9.1	\$10.22
Slender wheatgrass - Primar	Agropyron trachycaulum	3.50	Native	Cool	12.9	\$5.40
FORBS:						
Alfalfa - AV-Heyday	Medicago sativa	6.50	Introduced	NA	31.3	\$12.96
SHRUBS & TREES (seed):						

TOTAL SEEDS/SQUARE FT. = 215.47 TOTAL POUNDS PLS/ACRE = 50.0 TOTAL SEED MIX COST/ACRE = \$80.55

NOTE: Seed mix totals are doubled automatically if any seeding method other than drill seeding is used.

B. SHRUB & TREE TRANSPLANTS

[illegible]

C. SEEDBED PREPARATION

Tilling method #1: chisel plowing *

\$53.95

#2:

D. SEED APPLICATION

Total cost/acre: \$53.95

[illegible]

Seeding method: drill seeding *

Total cost/acre: \$60.23

E. FERTILIZING

FERTILIZER / SOIL AMENDMENT		UNITS/ACRE	UNIT	\$/UNIT	\$/ACRE
Materials used #1:	ammonium nitrate (33-0-0) *	200.00	pound	\$0.21	\$42.00
#2:					
#3:					
Total materials cost/acre:					\$42.00

Application method #1: hand held broadcast spreader *

\$101.63

#2:

Total application cost/acre: \$101.63

F. MULCHING

	MULCH / NETTING / OTHER MATERIALS	UNITS/ACRE	UNIT	\$/UNIT	\$/ACRE
Materials used #1:	straw (delivered) - ton *	2.00	ton	\$75.28	\$150.56
#2:					
#3:					
#4:					
	Total materials cost/acre.				\$150.56

Application method #1: power mulcher (hay spr. 1" deep) **

\$60.11

#2: crimping (with tractor) *

\$41.41

#3:

Total application cost/acre: \$101.52

G. JOB COST

Total area to be seeded: 30 00 acres.

Total \$/acre : \$590.44 Total Initial Job Cost= \$17,713.31

Estimated failure rate: 25.00% of area.

Total \$/acre* : \$590.44 Total Reseeding Costs = \$4,428.33

- * Reseeding cost items: A C D E F

GRAND TOTAL JOB COST = \$22,141.63

ESTIMATING FORM - EQUIPMENT MOBILIZATION / DEMOBILIZATION

Task #... 4 Prep. by CLK Filename..M341-4

Date.... 07-May-97 Permit # M-77-341 Mine.....Larimer County Quarry

Permit Action..... Succession of Operations

Task Description..... Mob/Demob Equipment to the site

HOURLY EQUIPMENT COST

===== NOTE - This is a list to select from, not a list of mandatory items to include. =====

Mob/Demob Eqp. -Tractor : 6x4, 75,000 lb GVW, 375 HP, diesel powered
 -Lt. Trailer : 25 ton folding gooseneck, drop deck
 -Med. Trailer : 50 ton folding gooseneck, drop deck
 -Hvy. Trailer : 120 Ton folding gooseneck, drop deck
 -Pilot Car : On-highway light duty truck, 4x2, 130 hp, 1/2 ton rating, gasoline powered
 -Hyd. Crane : Grove RT58D rough terrain hydraulic crane, 20 ton capacity, 125 hp, 60 ft. boom
 -Fuel Truck : 6x4, 3,600 gallon capacity, 210 HP, diesel powered
 -Lube Truck : 6x4, 2,500 gallon capacity, 210 HP, diesel powered
 -Flatbed Truck: 20,000 lb GVW, 175 HP, diesel powered

Last Update:

December, 1994

Cost Breakdown:	Lt. Rig <=25 T.	Med.Rig 26-50 T.	Hvy.Rig > 50 T.	Pilot Car	Hydraulic Crane	Fuel Truck	Lube Truck	Flatbed Truck
Ownership Cost/hr =	\$27.88	\$31.23	\$38.36	\$1.81	\$19.89	\$6.95	\$12.79	\$5.71
Operating Cost/hr =	\$26.84	\$29.29	\$34.27	\$5.12	\$23.40	\$18.53	\$24.52	\$8.00
Operator Cost/hr =	\$21.40	\$22.03	\$22.03	\$21.24	\$20.86	\$21.24	\$21.24	\$21.24
Helper Cost/hr =	\$20.60	\$21.24	\$21.24	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
Total =	\$96.72	\$103.79	\$115.90	\$28.17	\$64.15	\$46.72	\$58.55	\$34.95

NON-ROADABLE EQUIPMENT:

Machine Description	Weight (tons)	Ownership Cost/hr	Haul Rig Cost/hr	Fleet Size (no. hauled)	Haul Trip Cost/hr	Return Trip Cost/hr	DOT Permit Cost/ea
Revegetation Equipment	15.00	\$30.05	\$96.72	1	\$126.77	\$96.72	\$0.00

Subtotals : \$126.77 \$96.72 \$0.00

ROADABLE EQUIPMENT:

sheet 2 of 2

Machine Description	Total Eqp. Cost/hr	Fleet Size (no. hauled)	Haul Trip Cost/hr	Return Trip Cost/hr
=====				

Subtotals :	\$0.00	\$0.00
-------------	--------	--------

MOB/DEMOB SUPPORT EQUIPMENT:

Non-Roadable Eqp. Description	Weight (tons)	Ownership Cost/hr	Haul Rig Cost/hr	Fleet Size (no. hauled)	Haul Trip Cost/hr	Return Trip Cost/hr	DOT Permit Cost/ea
=====							

Subtotals :	\$0.00	\$0.00	\$0.00
-------------	--------	--------	--------

Roadable Eqp. Description	Total Eqp. Cost/hr	Fleet Size (no. hauled)	Haul Trip Cost/hr	Return Trip Cost/hr
=====				

Subtotals :	\$0.00	\$0.00
-------------	--------	--------

EQUIPMENT HAUL DISTANCE & TIME

=====

Nearest major city or town within project area region: Lyons

Total one way travel distance =	15.0 miles.	Average travel speed =	30.00 mph.
---------------------------------	-------------	------------------------	------------

Job Time - Non Roadable Equip.=	0.50 hours load	Roadable Equip.=	N/A hours load
	0.50 hours haul		0.50 hours haul
	0.50 hours unload		N/A hours unload
	0.50 hours return		0.50 hours return

JOB COST	Total Mob/Demob Cost =	\$477.03
----------	------------------------	----------

=====

=====

NOTE: Non-roadable equipment (haul rig required to transport) mob/demob costs based on 2 round trips, each trip consisting of a one-way loaded haul and a one-way empty return. Roadable equipment (no haul rig required) costs based on one round trip. Colorado DOT requires special permits for oversize equipment on certain specified road segments within the State. Separate permits are required for each rig on each loaded trip. Additionally, pilot cars (one or two per rig depending on degree of oversize) are also required for oversize equipment hauling, and loading/unloading times must be increased substantially for equipment which must be partially dismantled for transport and re-assembled at the job site. Costs for lifting equipment and other support equipment needed for this work should be included in the mob/demob costs.

PERMIT NUMBER : M-77-341 PREP. BY: . CLK FILENAME: M341-0

DATE : 07-May-97 OPERATION: Larimer County Quarry

PERMIT ACTION : Succession of Operations

GRAND TOTAL BOND AMOUNT : \$35,444

I. DIRECT COSTS

A. EARTHWORK - BACKFILLING & ROUGH GRADING

[illegible]

Subtotal (A) :

B. EARTHWORK - HIGHWALL REDUCTION

[illegible]

Subtotal (B) :

C. EARTHWORK - WASTE PILE COVER PLACEMENT

[illegible]

Subtotal (C) :

[illegible]

=====

[illegible]

=====

[illegible]

=====

Task No.	Task Description	Cost (\$)

=====

Task No.	Task Description	Cost (\$)

Subtotal (H) :

[illegible]

Subtotal (I) :

[illegible]

Subtotal (J):

K. PORTAL/SHAFT SEALING

Task No.	Task Description	Cost (\$)

Subtotal (K):

=====

L. DRILL HOLE/MONITORING WELL SEALING

Task No.	Task Description	Cost (\$)

Subtotal (L):

=====

M. MISCELLANEOUS RECLAMATION TASKS

Task No.	Task Description	Cost (\$)
	Demolition	
3	Seeding	\$29,522
	Fencing	
4	Mob/Demob	\$477

Subtotal (M): \$29,999

=====

TOTAL DIRECT RECLAMATION COSTS (subtotals A through M): \$29,999

=====

II. INDIRECT COSTS

=====

A. CONTRACTOR'S OVERHEAD & PROFIT

Item No.	Item Description	Cost (\$)
1.	Public Liability Insurance.... 1.550% of dir.	\$465
2.	Contractor's Performance Bond 0.975% of dir.	\$292
3.	Contractor's Profit..... 10.00% of dir.	\$3,000
4.	Job Superintendent..	

Subtotal (A): \$3,757

=====

TOTAL CONSTRUCTION CONTRACT AMOUNT (direct plus O & P): \$33,757

=====

B. DMG PROJECT ADMINISTRATION EXPENSES

Item No.	Item Description	Cost (\$)
1.	Minerals Program Adm 5.00% of cntr.	\$1,688

NET INDIRECT COST PERCENTAGE: 18.15% Subtotal (B): \$1,688

=====

TOTAL INDIRECT RECLAMATION COSTS (subtotals A through B): \$5,445

=====

TOTAL PERFORMANCE BOND AMOUNT (direct plus indirect costs): \$35,444

=====